

Asphalt R&R

Removal and Replacement of asphalt surface.

- Removal of existing asphalt.
- Regrading of existing base stone.
- Additional base stone added.
- Replacement of new commercial grade hot mix asphalt installed in **two** lifts
1100B or equivalent used for first lift.
1100T or equivalent used for final lift.

Total average asphalt paving depth of new driveway 3.5 inch

Asphalt Installation/Modification

- labor charge

Sub Base Work

- Existing grass removed (if needed), hauled offsite.
- Existing sub-grade compacted and new base stone (21AA) added, roller and/or plate compacted, graded and leveled.
- sub base aggregate installed at 4 inches
- Roller compacted, edges packed.